



Fire Rating





HPVA Laboratories 1825 Michael Faraday Drive, Reston, VA 20190-5350 PHONE 703-435-2900 FAX 703-435-2537



Report On Critical Radiant Flux of Floor-Covering Systems Using a Radiant Heat Energy Source As Determined By ASTM E 648 Test Method

PREPARED FOR:

Vintage Hardwoods LLC

Scottsdale, AZ

TEST NUMBER: FRP-929

Revival European Oak Engineered Hardwood Flooring

Date of Issue: 7/17/2015





HPVA Laboratories 1825 Michael Faraday Drive, Reston, VA 20190-5350 PHONE 703-435-2900 FAX 703-435-2537



I. SCOPE

This report contains the reference to the test method, purpose, test procedure, preparation and conditioning of test samples, description of materials, test and post test observation data, and test results.

II. TEST METHOD

The test was conducted in accordance with ASTM Designation E 648, "Standard Method of Test for Critical Radiant Flux of Floor Covering Systems Using a Radiant Heat Energy Source." The test is also described by NFPA No. 253.

III. PURPOSE

The purpose of the test is to determine the critical radiant flux of horizontally-mounted floor covering systems exposed to a flaming ignition source in a graded radiant heat energy environment maintained in a test chamber. The specimen may be mounted over underlayment, a simulated concrete structural floor, bonded to a simulated structural floor, or otherwise mounted in a typical and representative way.

The test method provides a basis for estimating one aspect of fire exposure behavior for floor covering systems. The imposed radiant flux is designed to simulate the thermal radiation levels likely to impinge on the floors of a building whose upper surfaces are heated by flames and/or hot gases from fully developed fire in an adjacent room or compartment. The method was developed to simulate an important fire exposure component of fires which may develop in corridors or exit ways of buildings and is not intended for routine use in estimating flame spread behavior of floor covering in building areas other than corridors or exit ways.

IV. TEST PROCEDURE

The basic elements of the test chamber are: 1) an air-gas, fueled radiant heat energy panel inclined at 30° to and directed at 2) a horizontally-mounted floor covering system specimen. The radiant panel generates a radiant energy flux distribution ranging along the 100-cm length of the test specimen from a nominal maximum of 1.0 watts/cm2 to a minimum of 0.1 watts/cm2. The test is initiated by open flame ignition from a pilot burner. The distance burned to flame-out is converted to watts/cm2 and reported as **critical radiant flux**.



HPVA Laboratories 1825 Michael Faraday Drive, Reston, VA 20190-5350 PHONE 703-435-2900 FAX 703-435-2537



Report on Critical Radiant Flux of Floor Covering Systems Using a Radiant Heat Energy Source as Determined by the ASTM E 648 Flooring Radiant Panel

Test Number:	FRP-929		Test Date:	07/17/15
		•		
Report Prepared For:	Vintage Hardwoods LLC Scottsdale,AZ			
neport i repared i or.				
Material Tested:	Revival European Oak Engineered Hardwood Flooring			ring
	Sa	mple Information:		
<u>Detailed Product</u>	Revival European Oak Engine	eered Hardwood Flooring		
<u>Description:</u>				
Sample Preparation:	The samples were nailed to 5	5/8" plywood by the manu	ufacturer.	
Sample Selection By:	Manufacturer		Flux Profile Run Date:	07/15/15
Number of Samples:	3		Conditioning Days:	8
Surface Exposed:			Sample Color:	Dark Brown
Average Thickness (in.):	1.261		Average Density (lbs/ft^2):	3.479
		Test Data		
	Burn 1	Burn 2	Burn 3	
Preheat Time (min):	2:00	2:00	2:00	
Starting Temp. (°C):	153	151	156	
Burn Length (cm):	33.1	38.2	33.5	
Time to Max Burn Length (min):	32.00	30.98	44.80	
		Test Results		
	Burn 1	Burn 2	Burn 3	
Critical Radiant Flux (W/cm2):	0.62	0.53	0.61	
	Average Critical Declient Flow (M/cm2)			
	Average Critical Radiant Flux (W/cm2):		0.59	
	Standard Deviation:		0.05	
	<u>Coefficient of Variation:</u>		9%	
Observations:	None.			
Remarks:	None.			
Test Operator:	СК			
Report Prepared By:			Report Reviewed By:	
Chris Pal			Brisn J. S.	nue

Manager of Fire Testing

Director of Testing, Certification, and Standards